ZONING DATA TABULATION

UPPER MERION TOWNSHIP
ZONING ORDINANCE

ARTICLE XX – C-2 COMMERCIAL DISTRICT

SECTION 165-112 – USE REGULATIONS:
165-113 – HEIGHT REGULATIONS

	REQUIRED	EXISTING	PROPOSED
MAX. BUILDING HEIGHT	3 STORIES OR 35 FT.	*28 FT.	BUILDING B/BUILDING A *28 FT/<35 FT.

SECTION 165-114 – AREA, WIDTH AND YARD REGULATIONS

	REQUIRED	EXISTING	PROPOSED
MIN. LOT AREA	10,000 S.F.	58,304 S.F. 51,157 S.F. (NET OF R/W)	58,304 S.F. 51,157 S.F. (NET OF R/W)
MIN. LOT WIDTH @ BUILDING LINE	70 FT.	390 FT.	390 FT.
MIN. FRONT YARD SETBACK	50 FT.	*5 FT.	50 FT./15 FT.
MIN. SIDE YARD SETBACK	15 FT.	31 FT.	31 FT/15 FT.
MIN. REAR YARD SETBACK	20 FT.	*34 FT.	*34 FT./35 FT.
MAX. BUILDING COVERAGE	N/A	8.34%	18.14%
MAX. IMPERVIOUS COVERAGE	N/A	73.46%	72.06%
MIN. GREEN SPACE	15%	26.80%	27.02%

*DENOTES EXISTING NON-CONFORMITY

GENERAL NOTES:

1. THE PURPOSE OF THIS PLAN IS TO DEPICT THE PROPOSED SITE IMPROVEMENTS FOR THE PROPOSED 5,765 SF (FOOTPRINT) LAUNDRY FACILITY AND CONVERSION OF AN EXISTING RESTAURANT TO OFFICE SPACE, INCLUDING, BUT NOT LIMITED TO, ACCESS DRIVES, PARKING AREAS, STORMWATER MANAGEMENT, GRADING, EROSION CONTROL, LANDSCAPING, AND LIGHTING.
2. TOPOGRAPHIC AND BOUNDARY INFORMATION WAS TAKEN FROM A PLAN OF SURVEY PREPARED BY CHESTER VALLEY ENGINEERS, A. DAVID SHEA, P.L.S. DATED JUNE 2, 2006. DATUM IS ASSUMED. (0.00ft. NOAD 1929 IS 329.81ft. UPPER MERION TWP. ELEVATION AT THE CENTER OF SHOEMAKER ROAD).
3. THERE ARE NO STREETS, RIGHT-OF-WAYS OR ANY LOTS FOR PUBLIC USE PROPOSED FOR DEDICATION BY THIS PLAN.
4. THE PROPERTY OWNER SHALL OBTAIN ANY AND ALL PERMITS REQUIRED FOR THE PROPOSED DEVELOPMENT AS SHOWN ON THIS PLAN.
5. PUBLIC WATER SERVICE IS TO BE PROVIDED BY AQUA PA. ALL WORK SHALL BE IN ACCORDANCE WITH THEIR STANDARDS AND SPECIFICATIONS WITH RESPECT TO THE FIRE FLOW AND PRESSURE WHICH PROVIDES THE SITE IS TO BE APPROVED BY PUBLIC BODIES.
6. D.L. HOWELL & ASSOCIATES, INC. DOES NOT GUARANTEE THE ACCURACY OF LOCATIONS OF ANY EXISTING SUBSURFACE UTILITY STRUCTURES SHOWN ON THE PLANS. NOR DOES D.L. HOWELL & ASSOCIATES, INC. GUARANTEE THAT ALL SUBSURFACE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES PRIOR TO THE START OF THE WORK.
7. LOCATION OF ALL EXISTING AND PROPOSED SERVICES ARE APPROXIMATE AND MUST BE CONFIRMED INDEPENDENTLY WITH LOCAL UTILITY COMPANIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION OR EXCAVATION. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE PENNSYLVANIA UTILITY CLEARANCE TO LOCATE THEIR FACILITIES PRIOR TO STARTING CONSTRUCTION IN ACCORDANCE WITH PENNSYLVANIA ACT 287 OF 1974 AS AMENDED BY PENNSYLVANIA ACT 187 OF 1996. "ONE CALL" SYSTEM NO EXTRA COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK. FORCE, SANITARY SEWER, WATER, ELECTRIC, GAS AND ALL OTHER UTILITY SERVICES CONNECTION POINTS SHALL BE CONFIRMED INDEPENDENTLY BY THE CONTRACTOR IN THE FIELD PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. ALL DISCREPANCIES SHALL BE REPORTED IMMEDIATELY IN WRITING TO THE ENGINEER. CROSSINGS WITH EXISTING UNDERGROUND INSTALLATIONS SHALL BE FIELD VERIFIED BY TEST PIT PRIOR TO COMMENCEMENT OF CONSTRUCTION.
8. UNLESS NOTED OTHERWISE ON THE PLANS OR IN THE PERMITS GOVERNING THE WORK, ALL CONSTRUCTION METHODS AND MATERIALS SHALL BE IN ACCORDANCE WITH THE FOLLOWING APPROPRIATE STANDARDS AND SPECIFICATIONS:
UPPER MERION TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE AND AMENDMENTS.
PADOT SPECIFICATION PUBLICATION, 408/2003 LATEST EDITION & ALL OF THE LATEST ADDENDA.
9. THE LIMITS OF DISTURBANCE SHALL BE STAKED IN THE FIELD AND INSPECTED PRIOR CONSTRUCTION FENCING PRIOR TO THE COMMENCEMENT OF CONSTRUCTION AND SHALL BE MAINTAINED DURING THE ENTIRE PERIOD OF CONSTRUCTION. NO VARIATION THEREFROM SHALL BE PERMITTED, UNLESS APPROVED BY THE TOWNSHIP ENGINEER OR WHERE SUBJECT TO FIELD MODIFICATIONS CONDITIONS AS HE MAY DETERMINE NECESSARY.
10. TOPOGRAPHIC SURVEYS OF ALL DRAINAGE FACILITIES AND BASINS SHALL BE SUBMITTED FOR REVIEW.
11. ALL DIMENSIONS ARE TO FACE OF CURB OR FACE OF BUILDING UNLESS NOTED OTHERWISE. SCALED DIMENSIONS SHALL NOT BE USED WITHOUT FIRST CONFIRMING THE ENGINEER OR ARCHITECT.
12. REPRESENTATIVES OF UPPER MERION TOWNSHIP AND/OR OTHER GOVERNMENTAL AUTHORITIES SHALL HAVE PERMISSION TO GAIN ACCESS TO THE STORMWATER BASIN THROUGH THE PROPERTY TO PERFORM INSPECTIONS, MAINTENANCE AND REPAIRS OF THE BASIN AS NECESSARY.
13. ON-LOT STORMWATER DEVICES SHALL NOT BE REMOVED, ALTERED OR RELOCATED BY THE LANDOWNER. IN THE EVENT OF THE FAILURE OF THE LANDOWNER TO COMPLY WITH THESE CONDITIONS AND RESTRICTIONS, THE TOWNSHIP SHALL HAVE THE AUTHORITY TO RESTORE SAID STORMWATER MANAGEMENT FACILITIES TO THEIR ORIGINAL STATE AND THE COSTS THEREOF SHALL BE ASSESSED TO THE LANDOWNER. THE TOWNSHIP, BEFORE IT MAY EXERCISE THIS RIGHT, SHALL NOTIFY THE LANDOWNER BY CERTIFIED MAIL OF ITS INTENTION TO DO SO. THE NOTICE SHALL SET FORTH IN WHAT MANNER THE OWNER HAS ALTERED THE STORMWATER MANAGEMENT FACILITIES, AND IF THE OWNER FAILS TO CORRECT THE ALTERATION SUBJECT TO THE NOTICE WITHIN THE TOWNSHIP'S OWN AND SOLE THEN THE TOWNSHIP MAY EXERCISE THE RIGHT.
14. WHERE A PROPOSED WALL HEIGHT EXCEEDS 30 INCHES (30") ON EITHER SIDE, A FOUR FOOT HIGH FENCE SHALL BE PROVIDED. ENGINEERING PLANS AND CALCULATIONS FOR THE PROPOSED RETAINING WALLS AND FENCES SHALL BE SUBMITTED TO THE TOWNSHIP ENGINEER FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION. THE PLANS AND CALCULATIONS SHALL BE PREPARED BY A PENNSYLVANIA REGISTERED PROFESSIONAL ENGINEER, AND THE ENGINEER OF RECORD SHALL PROVIDE TO THE TOWNSHIP SIGNED AND SEALED VERIFICATION THAT ALL WALLS HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE APPROVED DESIGN. NOTWITHSTANDING, RETAINING WALL CONSTRUCTION SHALL BE OBSERVED AND INSPECTED BY THE WALL DESIGN ENGINEER OF RECORD AND A CERTIFICATE OF AS-BUILT SHALL BE SUBMITTED TO THE ENGINEER FOR EACH WALL.
15. ALL ON-SITE UTILITY LINES, INCLUDING BUT NOT LIMITED TO ELECTRIC, GAS, STREETLIGHT SUPPLY AND TELEPHONE, SHALL BE PLACED UNDERGROUND. DEDICATION OF ALL UTILITIES SHALL BE IN STRICT ACCORDANCE WITH THE REGULATIONS, STANDARDS AND SPECIFICATIONS OF THE TOWNSHIP, MUNICIPAL AUTHORITY OR OTHER PUBLIC UTILITY CONCERNED. A PLAN SHOWING THEIR LOCATION MUST BE SUBMITTED TO THE TOWNSHIP PRIOR TO CONSTRUCTION.
16. ALL CURB RADII SHALL BE 5' UNLESS OTHERWISE NOTED.
17. THIS PROPERTY IS LOCATED OUTSIDE OF 500 YEAR FLOOD PLAIN, FLOOD HAZARD ZONE X, AS PER THE MITCHELL FLOOD INSURANCE RATE MAP FOR MONTGOMERY COUNTY, PA. MAP NO. 42091C0091G, PANEL 353 OF 451, DATED AUGUST 8, 2013. FLOOD PLAIN BOUNDARIES SHOWN HEREON WERE LOCATED BASED ON THE CROSSSECTIONS AND ELEVATIONS PROVIDED WITH THE ABOVE REFERENCED FIRM MAP THEN ADJUSTED TO FIT THE BASE PLAN SHOWN.
18. THE APPLICANT SHALL PROVIDE THE REQUIRED FEE IN LIEU OF PARKLAND PURSUANT TO SECTION 165-43 OF THE UPPER MERION ZONING ORDINANCE.
19. THE PROPERTY OWNER SHALL HAVE THE RESPONSIBILITY FOR THE PERPETUAL MAINTENANCE OF THE PERMANENT STORMWATER MANAGEMENT FACILITIES. NO CHANGES SHALL BE MADE TO THE STORMWATER MANAGEMENT FACILITIES OR FINISHED GRADE WITHOUT HAVING PRIOR WRITTEN APPROVAL FOR THE TOWNSHIP A BUILDER'S EXPENSE IS HEREBY DEMANDED GIVING THE TOWNSHIP THE RIGHT, BUT NOT THE OBLIGATION, TO ENTER THE PROPERTY TO PERFORM ANY REQUIRED MAINTENANCE WHERE HE/SHE NOT BEEN PROPERLY PERFORMED IN A TIMELY MANNER. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR THE COST OF ANY MAINTENANCE WHICH IS PERFORMED BY THE TOWNSHIP. THE TOWNSHIP SHALL HAVE THE PROPERTY FOR SAID COSTS UNTIL THE TOWNSHIP HAS BEEN REIMBURSED IN FULL.
20. THE ENGINE SHALL BE DISPATCHED ONCE A YEAR AND AFTER EACH STORM EVENT GREATER THAN 100 YEARS TO ENSURE HOW OF THE ORIFICES ARE UNCLOGGED. THE BASIN SHALL BE FLUSHED EVERY TWO YEARS TO PREVENT THE BUILDUP OF DEBRIS AND SEDIMENT. SAID SEDIMENT SHALL BE DISPOSED OF AT AN APPROVED SITE.
21. THERE SHALL BE NO ENCROACHMENT UPON ADJACENT PROPERTIES DURING CONSTRUCTION WITHOUT FIRST OBTAINED WRITTEN PERMISSION FROM THE OWNER OF THE ADJACENT PROPERTY.
22. SIX (6) INCHES OF TOPSOIL SHALL BE PLACED ON ALL LAWN AREAS.
23. THIS PLAN WAS PREPARED UTILIZING A COORDINATE TO ANGLE TITLE ISSUED BY FIRST AMERICAN TITLE INSURANCE COMPANY. THE COMMITMENT NUMBER IS 4577174, EFFECTIVE DATE, JULY 25, 2012. SCHEDULE B-SECTION 2 OF SAID CERTIFICATE CONTAINS THE FOLLOWING SURVEY RELATED MATTERS (ITEM NUMBERS CORRESPOND TO THE INFORMATION EXCEPTIONS MENTIONED):
7. AGREEMENT IN DEED BOOK 197 PAGE 402.
(PLEASE SEE EXHIBIT AND NOTE, NO EVIDENCE OF HAZARDS ON PARCEL PROPERTY)
8. CONDITIONS IN DEED BOOK 977 PAGE 482.
(SUBJECTS TO BUILDING AND ZONE, NO EVIDENCE OF PARKING ON STREET OR SURFACE PROBLEMS)
9. RELEASE AND EASEMENT IN DEED BOOK 3491 PAGE 173.
(AN ACCESS EASEMENT ALONG EAST PROPERTY LINE, PLOTTED)
10. EASEMENT AGREEMENT IN DEED BOOK 3699 PAGE 161.
(ON POINT OF WAY EXISTS SO LONG AS ACCESS TO PARKING IS LIVE. THIS EASEMENT IS FOR ADJACENT PROPERTIES 58-00-16777-03-1, 58-41A-27 & 58-41-29. DOES NOT AFFECT SUBJECT PREMISES)
11. RIGHTS OF OTHERS IN AND TO A 30 FOOT WIDE RIGHT OF WAY. (EXISTING DRIVEWAY)
12. EASEMENT AGREEMENT IN DEED BOOK 5034 PAGE 788.
(REMOVED EASEMENTS ON EAST SIDE OF HENDERSON ROAD. DOES NOT AFFECT SUBJECT PREMISES)
13. EASEMENT AGREEMENT BETWEEN THE MANUFACTURERS LIFE INSURANCE CO. AND PUBLICAKE PARTNERSHIP DATED 4/30/1984, RECORDED IN DEED BOOK 5049 PAGE 78.
(CONSISTING OF WIDE ACCESS EASEMENT OVER PARCEL 58-00-03780-00-8, THE MAP # 58-41A-29, 688-8 NO WIDE TOTAL OVER EASEMENT CONTINUES ON THE EASTERN SIDE BOTH AT THE INTERSECTION OF THE SUBJECT PREMISES. BOTH PLOTTED.)
14. THE DETAILED SOIL TESTING REPORT PREPARED BY A PA. PROFESSIONAL ENGINEER MUST BE SUBMITTED FOR REVIEW PRIOR TO CONSTRUCTION FOR THE SOILS ALONG THE REAR PROPERTY LINE.
15. EROSION CONTROL MEASURES SHALL BE REVIEWED DURING THE BUILDING PERMIT PROCESS TO ENSURE ADEQUATE PROTECTION FROM SILTATION TO PRESERVE.

PARKING REQUIREMENTS:

SECTION 165-191.B OFF-STREET PARKING

TYPE OF USE:	PARKING REQUIREMENT:	REQUIRED:	TOTAL SPACES PROVIDED:
PERSONAL SERVICES LAUNDRY	1 SPACE/150 S.F. GLA SERVICE AREA	3,918 S.F. GLA = 26.12	27 SPACES
OFFICE	1 SPACE/EMPLOYEE 4 SPACES/1,000 S.F. GLA	1 EMPLOYEES = 1 773 S.F. = 3.09	1 SPACES 3 SPACES
OFFICE	4 SPACES/1,000 S.F. GLA	4,340 S.F. = 17.32	17 SPACES
		47.53 OR 48 SPACES	48 SPACES
HANDICAPPED PA8OWA2		28-50 RETAIL/SERVICE SPACES = 2 REQ. —2 SPACES PROVIDED	

WAIVERS GRANTED: (JANUARY 26, 2012)

1. A WAIVER HAS BEEN GRANTED FROM SECTION 165-31.1.A(2)(b) OF THE UPPER MERION TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCES TO ALLOW LESS THAN A 15' TOP BUFFER ALONG THE REAR PROPERTY LINE.
2. A WAIVER HAS BEEN GRANTED FROM SECTION 165-19.A(2) OF THE UPPER MERION TOWNSHIP STORMWATER MANAGEMENT ORDINANCES TO ALLOW GRADING WITHIN FIVE (5) FEET OF THE PROPERTY LINE.
3. A WAIVER HAS BEEN GRANTED FROM SECTION 165-31.1.A(2)(a) OF THE UPPER MERION TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCES TO ALLOW A PLANTING AREA ADJACENT TO A BUILDING BE LESS THAN TEN (10) FEET IN WIDTH.


SHOEMAKER ROAD
EXISTING R/W
98.00'
N 50°52'00" E 354.50'
N48° 05' 32"E 208.18'
R=500.00'
Δ=13°00'02"
L=113.46'
CH=113.22'
N41°35'28E
N30°19'00"
36.30'
32.64'
PROPOSED BUILDING 'A'
LAUNDROMAT FACILITY
5,765 SF. FOOTPRINT
3,918 SF. SERVICE AREA (GLA)
FF=227.46
773 SF. OFFICE
(2ND FLOOR)
GROSS LEASABLE AREA:
2,634 SF 1ST FLOOR
1,107 SF SECOND FLOOR
801 SF BASEMENT
F.F.=219.55
BUILDING HEIGHT=25'
PROP. ADA PERFORATION TYPE 2 PARTIAL CURB RAMP W/ DETECTABLE WARNING SURFACE
PROPOSED FIELD 40 SPACES
PROP. SIGN "STOP" (TYP.)
PROP. SIGN "RESERVED PARKING - VAN ACCESSIBLE"
6" CONC. SIDEWALK
5' CURB TAPER
5' WIDE CONC. SIDEWALK
ENTRANCE
PROP. SIGN "RESERVED PARKING"
PRIMARY ENTRANCE
ACCESS EASEMENT DB 5616 PG. 1749 PB A-34 PG. 19
10' WIDE DRAINAGE EASEMENT DB 5616 PG. 1749 PB A-34 PG. 19
6" CONC. SIDEWALK
CONC. STEPS W/HANDRAILS
6" R.C. W/ DETERMINATE WARNING SURFACE
8'X15' TRASH ENCLOSURE
CONC. BLOCK RETAINING WALL
FENCE/RAILING
SPK(P) 101.48
M 00.00.15 S
126.54'
N 43°44'57" W 210.57'
C-2 ZONING DISTRICT
M 00.6P.15 S
266.99'
N31°49'00" E 30.04'
LP#N(S)
LP#N(P)
58-00-16777-03-1
58-41A-27
N/A VILLAGE MART ASSOCIATES
DB 4825 PG 87
(RETAIL USE)
58-00-03780-00-8
58-41A-29
N/A 688 HENDERSON L.P.
DB 5563 PG 1888
(OFFICE/COMMERCIAL USE)
58-00-17671-00-7
58-41A-7
N/A KOF ASSOCIATES
DB 2691 PG 2045
58-00-17678-00-3
58-41A-21
N/A QUAN L.P.
DB 5363 PG 1868
(OFFICE/COMMERCIAL USE)
CONC. WALK
STORM MH RIM 330.15±
INV 320.75±
INV 320.60±
STORM MH RIM 330.15±
INV 320.75±
INV 320.60±
STORM MH RIM 329.85
INV 320.35
STORM MH RIM 330.10
INV 320.70
STORM MH RIM 329.85
INV 320.35
STORM MH RIM 329.85
INV 320.35
STORM MH RIM 329.85
INV 320.35



Lennox Design Studios
2801 Sorrel Drive
Towamencin, Pennsylvania 19403
Phone: 610.277.4953 Fax: 610.277.4954
www.lennoxdesignstudios.com

Project Manager/Designer

Architect/Engineer Seal

Shoemaker Apartments

Project Client:
Bilal Inc
520 Shoemaker Road
King of Prussia, PA 19406

Project Location:
520 Shoemaker Road
King of Prussia, PA 19406

DRAWN BY: CPI
CHECKED BY:
DATE: 12-1-2020
PROJECT #: 2020-02
FILE: Shoemaker.dwg

CONTENTS:
PARTIAL SITE PLAN
SCALE: 1"=10'

A-000